


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO.
Farm- Oswald "D" No. 1

SEC. 2 T. 12 R. 16W
NW NW SE

Total Depth. 3387'
Comm. 9-26-59 Comp. 10-3-59
Shot or Treated.
Contractor.
Issued. 11-28-59

County Ellis
KANSAS



Elevation. 1801' DF

Production. Dry

CASING:

8 5/8" 172' cem w/140 sx.

Figures Indicate Bottom of Formations.

clay & rock	70
shale & shells	460
shale & sand	635
sand & red bed	960
Anhydrite	998
shale	1120
shale & shells	1635
lime & shale	2005
lime	2090
lime & shale	2885
lime	3387 RTD
Total Depth	

TOPS:

Anhydrite	960
Topeka	2706
Heebner	2972
Toronto	2991
Lansing	3018
Simpson Sand	3372
Arbuckle	3377

DST #1 3006-3037', op 14 min., had weak blow for 6 mins., rec. 5' mud, all pressures 0#.

DST #2 3199-3218', op 1 hr., had an intermittent blow for 1 hr., rec. 20' very slightly oil cut mud, IBHP 120#, FBHP 0#.