

Plotted *gr*

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

J.J.HALL ET AL.
Oswald ~~"B"~~ No. 1

SEC. 2 T. 12 R. 16 W.
NE SW SW

County Ellis.

Total Depth. 3437
Comm. 9-26-41 Comp. 12-1-41
Shot or Treated.
Contractor. J.J.Hall.
Issued. 12-2-42

CASING.

12 $\frac{1}{2}$ " 95' cemented. Left in.
5 $\frac{1}{2}$ " 3192' cemented. Left in 1850

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

shale shell & iron	266
sand	300
shale and shells	1000
lime	1048
shale and lime	1405
salt	1500
shale and lime	1760
shale	1765
sdv lime	1785
shale	1800
shale and lime	1920
lime	2020
shale and lime	2031
lime	2073
lime shale & red rock	2223
shale and lime	2706
sdv shale	2752
shale and lime	2785
lime	2964
shale and lime	3066
lime	3089
shale	3094
lime	3105
shale green	3108
lime	3126
broken lime	3131
lime	3139
lime and shale	3148
lime	3193
shale	3197
lime	3205
shale	3209
lime	3230
broken lime	3245
lime	3251
broken lime	3256
shale	3266
lime	3290
shale	3295
lime	3305
shale and red rock	3323
lime and shale	3346
conglomerate	3366
shale green	3369
Various colored shale	3372
shale green and lime	3377
lime	3382
Various col. shale	3385
lime and shale	3390
lime	3394
shale green	3396
sand	3399
lime	3428
water sand	3436
HFW	
lime	3437
Total Depth.	

Water and Oil Record.

SHOW OIL AND WATER	2801-2805
SHOW OIL AND WATER	3095-3105
" " " "	3111-3116
" " " "	3396-3399
Holefull of water	3428-3436

Plugged.

