

9-12-16W
P1

WILLIAMSON DRILLING, INC.

5501 NAVAJO

GREAT BEND, KANSAS 67530

DRILLERS' WELL LOG X

DATE COMMENCED: March 24, 1985
DATE COMPLETED: March 30, 1985

Grady Bolding Corporation
Don #1
SE NE NW
Sec. 9, T12S, R16W
Ellis County, Kansas

Elevation: 1855 G.L.
1860 K.B.

Surface Pipe: Ran 25 Jts. New 23# 8 5/8"
casing, Set @ 1029'. Cemented w/425 Sks.
50/50 Poz 2% Gel 3% CC.

Production Casing: Ran 81 Jts. New 9.5#
4 1/2" casing. Set @ 3420'. Cemented w/
150 Sks. Sure-Fill Cement.

0 - 725' Surface Soil, Postrock
725 - 1021' Redbed
1021 - 1060' Anhydrite
1060 - 2720' Shales w/Lime Stringers
2720 - 3030' Lime & Shale
3030 - 3070' Shale W/Lime
3070 - 3370' Lime
3370 - 3420' Conglomerate
3420 - 3470' Dolomite
3470' R.T.D.

JUL 18 1985
State Geological Survey
WICHITA BRANCH

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss.

Terry L. Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Terry L. Williamson
Terry L. Williamson

Subscribed and Sworn to before me this 1st. day of April 1985.

My Commission Expires: