


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock, Wichita, Kansas

Company - W. E. WICKIZER ET AL  
 Farm - Weigel No. 1

SEC. 19 T. 12 R. 16W  
 CE $\frac{1}{2}$  NW SE

Total Depth. 3628  
 Comm. 4-28-50 Comp. 5-11-50 ✓  
 Shot or Treated.  
 Contractor. Glenn Nye Drlg.  
 Issued. 8-12-50

County. Ellis  
 KANSAS



CASING:  
 8 5/8" 137'

Elevation. 2087

Production. Dry

Figures Indicate Bottom of Formations.

surf rock, soil	55
shale blue	125
shale blue, shells	136
shale blue	345
shale	385
sand, shale	650
lime sdy, pyrite	675 ✓
lime, pyrites iron	695 ✓
shale blue, sand	
strks.	790
sand	885
redbed	1045
redbed, shale iron	
stks	1255 ✓
anhyd.	1290
redbed, shale	1535
shale, shells	1690
salt, shale	1820
shale, shells, iron	
pyrite	1930 ✓
shale, lime, shells	1965
lime, shale	2670
shale, shells	2740
lime, shale	3342
lime	3590
lime, shale	3617
lime	3628
Total Depth	

Tops:  
 Heebner 3278  
 Lansing 3326  
 Arbuckle 3607

D.S.T. 3608-17  
 open 15" rec. 7' mud.  
 D.S.T. 3346-61 open 15"  
 rec. 210' wtr.