


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- VYE-MALLONEE
Farm- Windholz "A" No. 2

SEC. 3 T. 12 R. 17W
NE SW SE

Total Depth. 3675'
Comm. 11-26-57 Comp. 12-11-57
Shot or Treated.
Contractor. Mallonee Drilling Co.
Issued. 8-1-58

County Ellis
KANSAS



Elevation. 2116' KB

Production. 50 LOPD

Figures indicate Bottom of Formations.

postrock	40
shale & lime rock	85
sand	100
shale, shells & sand	222
shale	670
sand & shale	980
red bed	1314
Anhydrite	1355
shale & shells	1730
salt & shale	1900
shale & lime	1985
lime	2110
lime & shale	2200
lime	2290
lime & shale	2370
lime	2435
shale & lime	2905
lime	2930
lime & shale	3095
lime	3150
lime & shale	3195
lime	3570
lime & shale	3600
lime	3675 RTD
Total Depth	

TOPS:

Heebner	3287
Toronto	3309
Lansing	3334
Base Kansas City	3567
Conglomerate	3596
Arbuckle	3600

DRILL STEM TESTS:

#1 3390-3421, op 1 hr, rec. 150' slightly
oil & gas cut watery mud, 120' oil & gas
cut watery mud, 60' heavy oil cut watery
mud, 60' oil cut water. BHP 685#.

#2 3421-3435, op 1 hr, rec. 4' oil cut
mud, 64' water. BHP 775#.

#3 3603-3620, op 2 hrs, rec. 2' oil, 30'
heavy oil cut mud, 60' oil cut mud. BHP 685#.

#4 3663-3675, op 1 hr, rec. 30' mud, slight
show oil, BHP 983#.