


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- VYE-MALLONEE
Farm- Windholz "B" No. 1

SEC. 3 T. 12 R. 17W
SW/2 E/2 SE/4

Total Depth. 3660'
Comm. 10-5-57 Comp. 10-19-57
Shot or Treated.
Contractor. MALLONEE DRILLING COMPANY, INC.
Issued. 1-4-58

County Ellis
KANSAS



CASING:

8 5/8" 213' cem. w/140 sx
5 1/2" 3658' cem. w/100 sx

Elevation. 2105' KB

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale & post rock	40
limestone & shale	70
sand	90
shale & shells	170
shale	213
shale & shells	530
shale & sand	650
sand	700
sand, shale & shells	820
sand	960
shale & shells	1140
red bed and shale	1304
anhydrite	1330
shale & shells	1955
lime & shale	1970
lime	2100
shale & shells	2160
lime & shale	2230
lime	2375
lime & shale	2585
lime	2650
lime & shale	2755
shale & shells	3035
lime	3235
lime & shale	3465
lime	3660 RTD
Total Depth	

TOPS:

Anhydrite	1304
Heebner	3278
Toronto	3300
Lansing K.C.	3326
Base K. C.	3558
Conglomerate	3577
Arbuckle	3588

D. S. T. #1. 3398-3420 Open 1 hr.
Rec. 180' gas, 210' heavy oil and
gas cut mud, 125' watery mud. BHP
883#.
D.S. T. #2. 3591-3605 Open 1 hr.
Rec. 22' mud. BHP 110#.
D.S.T. #3. 3591-3620 Open 1 hr.
Rec. 25' mud. BHP 114#.
D.S. T. #4. 3591-3651 Open 1 1/2
hr. Rec. 55' mud. BHP 126#.