

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas


Company: MURFIN DRILLING CO.
 Farm: Windholtz No. 1

SEC. 3 T. 12 R. 17W
 NW NW SW

Total Depth: 3688'
 Comm: 2-7-59 Comp. 2-16-59
 Shot or Treated:
 Contractor: Murfin Drilg. Co.
 Issued: 4-4-59

County Ellis

KANSAS



CASING

10 3/4" 187' cem w/150 sx.

Elevation. 2125' KB

Production. Dry

Figures indicate Bottom of Formations.

surface hole	187
shale	400
shale - shells	650
sand - shale	750
shale - shells	875
sand	995
red bed - shells	1340
Anhydrite	1379
shale - shells	1680
salt - shells	1930
shale - lime shells	2045
lime - shale	2780
shale - lime shells	3020
shale - lime	3210
lime	3325
lime - shale	3415
lime	3575
lime - shale	3635
Arbuckle	3688
Total Depth	

TOPS:

Topeka	3073
Heebner	3310
Toronto	3331
Lansing-Kansas City	3355
Base Kansas City	3589
Conglomerate	3616
Arbuckle	3635

DST #1 3637-45', op 1 hr, rec. 10' mud.
 IF 0#, FF 0#, BHP 0#/20 min.

DST #2 3637-60', op 1 hr., rec. 25' mud
 w/a few specks of oil. IF 0#, FF 0#,
 BHP 380#/20 min.

DST #3 3637-80', op 1 1/2 hrs., rec. 110'
 watery mud w/a few specks of dead oil.
 IF 0#, FF 0#, BHP 640#/30 min.