


Plotted Texas CO.

PHILLIPS PETRO.
S. Bertha No. 2.

SEC. 5 T. 12 R. 17W
NEo SE
330' NL 261' EL SE

County. Ellis

Total Depth. 3520'
Comm. 4-11-37 Comp. 4-30-37
Shot or Treated. 2000 Gals.
Contractor. Manning & Martin
Issued. 7-3-37



CASING:

10 3/4" 1081'
7 " 3506'

JUL 3 1937

Elevation.

Production. Pot. 2423 B.

Figures Indicate Bottom of Formations.

shale & shells	226
shale, lime & sand	545
shale & shells	970
shale red	1045
sand & iron	1065 ✓
shale red	1090
red rock	1155
red rock & shells	1250
anhydrite	1291
shale & shells	1550
salt	1719
shale	1725
salt	1860
shale & lime	2018
lime	2060
lime & shale	2166
lime	2430
shale & lime	2690
lime	2725
lime & shale	2815
shale	2835
lime	2868
lime & shale	3038
lime	3232
lime & shale	3246
coring	3297
lime	3520
Total Depth.	

Lansing 3288-3311
Siliceous 3506-3520