


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - ISERN DRILLING CO., ET AL
Farm - Dreiling No. 1

SEC. 8 T. 12 R. 17 W
SE SE NE

Total Depth. 3711 PB 3480
Comm. 6-25-51 Comp. 7-25-51
Shot or Treated.
Contractor.
Issued. 8-15-51

County. Ellis
KANSAS



CASING:
8 5/8" 170'
5 1/2" 3636'
Recovered 2726.40'

Elevation. 2136 DF
2138 RB (end)
Production. dry

lime, clay	75
shale, shells	500
sand	575
shale, shells	655
sand	745
shale, shells	795
sand	810
shale, shells	880
sand	1010
shale, shells	1230
sand, shale	1240
shale, shells	1353
anhydrite	1383
shale, shells	1745
salt	1940
lime, shale	2485
shale, shells	2600
shal, lime	3000
shale, shells	3080
lime, shale	3310
lime RTD	3644

CABLE TOOL WORK:
Movec in cable tools,
bailed hole, drilled cement
and cleaned out hole to RTD.

lime	3658
Acidized w/2500 gals acid little oil	
lime	3674
Shot w.30 gallons nitro. Little oil	
lime	3711
Total Depth	
Plug-back 3480	

Tops: Corr. 2' to DF	
Topeka	3094
Heebner	3329
Base Oread	3368
Lansing	3376
Base K.B.	3612
Arbuckle	3634

3711 Mostly water
Set plug at 3480
perforated & acidized
w/1000 gallons.
No show. 3480
plug-back depth D & A