

State Geological Survey

KANSAS DRILLERS LOG WICHITA, BRANCH

S. 8 T. 12 R. 17 ^R/_W

Loc. SW SE SW

County Ellis

API No. 15 — 051 — 21,021
County Number

Operator
Isern Petroleum Co.

Address
Box 486 Ellinwood, Kansas 67526


Well No. #5 Lease Name Schmeidler "B"

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Duke Drilling Company Geologist Warren O. Johnson

Spud Date June 11, 1975 Total Depth 3672 P.B.T.D. 3672

Date Completed June 17, 1975 Oil Purchaser Koch Oil Company



Locate well correctly

Elev.: Gr. 2157

DF 2160 KB 2162

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	245	common	125	2% gel 3% C.C.
Prod. Casing	7 7/8	4 1/2	10	3668	with 100 salt latex and 10 bbl salt flush DV Tool cemented with 50=50 pozmix with	375	Common + 150 Gal salt flush Opened with 6% gel.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			Open Hole		
Size 2 3/8 EUE	Setting depth 3669	Packer set at none			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 7-9-75	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 30 bbls. Gas None MCF Water 70 bbls. Gas-oil ratio None CFPB
Disposition of gas (vented, used on lease or sold) none	Producing interval (s) 3668 to 3672

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Isern Petroleum Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

Well No. 5 Lease Name Schmeidler "B"

s 8 T 12 R 17^E_W Ellis County, Kansas

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	0	40	Anhydrite	1367
Shale, Sand streaks	40	70	Topeka	3115
Shale & Shells	70	325	Heebner	3351
Shale	325	650	Lansing	3398
Sand, Shale Streaks	650	1040	Simpson Shale	3643
Red Bed	1040	1330	Arbuckle	3665
Lime and Shale	1330	1367	R. T. D.	3670
Anhydrite	1367	1415		
Shale, Shells	1415	2070		
Lime and Shale	2070	3150		
Lime	3150	3351		
Shale	3351	3355		
Lime	3355	3643		
Shale	3643	3665		
Dolomite	3665	3670		
R. T. D.		3670		



USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<u>Walter E. Schaub</u> Signature
	<u>General Manager</u> Title
	<u>July 1975</u> Date

31412