


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ISERN DRILLING CO.
Farm- Schmeidler "B" No. 2

SEC. 8 T. 12 R.17W
NW SE SW

Total Depth. 3666
Comm. 11-20-52 Comp. 12-4-52
Shot or Treated.
Contractor.
Issued. 6-20-53

County Ellis
KANSAS



Elevation. 2142

Production. 265 bbls.

CASING:

8 5/8 190' w/ 150 sx cement
5 1/2 3664'

Figures Indicate Bottom of Formations.

cellar	10
post rock & clay	50
shale & shells	520
sand	575
shale & shells	666
sand	758
shale & shells	870
sand	1015
shale & shells	1365
anhydrite	1400
shale & shells	1740
salt	1925
shale & shells	1955
shale & lime	2420
lime	2665
shale & lime	3190
lime	3342
Heebner	3348
lime	3640
Simpson	3664
Arbuckle	3666
Total Depth	

SCOUT TOPS:

Anhydrite	1365
Heebner	3342
Lansing	3389
Simpson	3640
Arbuckle	3660

DST #1: 3473-90; open 1 hr. rec.
180' salt water, 700' gas.