


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
**500 East Murdock, Wichita, Kansas**

Company- GLICKMAN OIL COMPANY  
 Farm- Rohleder No. 1

SEC. 9 T. 12 R. 17W  
 SE SE SE

Total Depth. 3756  
 Comm. 1-25-52 Comp. 2-7-52  
 Shot or Treated.  
 Contractor. Veeder  
 Issued. 3-15-52

County Ellis  
 KANSAS



CASING:  
 8 5/8" 190' cem 125 sx.

Elevation. 2147

Production. dry

Figures indicate Bottom of Formations.

|                      |      |
|----------------------|------|
| cellar               | 9    |
| clay                 | 20   |
| rock                 | 35   |
| sand                 | 40   |
| shale, sh ells, sand | 65   |
| sand, shale, rock    | 150  |
| shale rock           | 190  |
| shale                | 380  |
| shale, shells        | 560  |
| sand, shale          | 690  |
| sand                 | 770  |
| shale, sand, iron    | 1015 |
| shale                | 1040 |
| shale, red rock      | 1368 |
| anhydrite            | 1407 |
| shale, shells        | 1700 |
| salt, shalt          | 1730 |
| shale, salt, shells  | 1980 |
| lime, shale          | 2125 |
| shale, lime, shells  | 2170 |
| lime, shale          | 3145 |
| lime                 | 3659 |
| cherty conglomerate  | 3718 |
| arbuckle lime        | 3756 |
| Total Depth          |      |

|              |      |
|--------------|------|
| Tops: Scout. |      |
| Topeka       | 3114 |
| Heebner      | 3365 |
| Lansing      | 3412 |
| Conglomerate | 3664 |
| Arbuckle     | 3720 |