

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Roth No. 1

SEC. 9 T. 12 R. 17W
NE NE NW

Total Depth. 3717'
Comm. 11-25-58 Comp. 12-3-58
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 1-31-59

County Ellis
KANSAS



CASING:

8 5/8" 199' cem w/160 sx.

Elevation. 2135' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	199
shale - shells	530
sand - shale	645
sand	750
shale - shells	890
sand	1050
red bed - shale	1357
Anhydrite	1396
shale - shells	1750
salt - shells	1890
salt - shale	1940
shale - lime shells	2305
lime	2385
lime - shale	3235
lime	3335
lime - shale	3505
lime	3600
lime - shale	3667
lime - Arbuckle	3717
Total Depth	

TOPS:

Anhydrite (scout)	1357
Topeka	3099
Heebner	3334
Toronto	3355
Kansas City-Lansing	3379
Base Kansas City	3611
Arbuckle	3667

DST #1 3669-75, op 1 hr, rec. 590' salt
water, IF 60#, FF 315#, BHP 990#/20 mins.