


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- DAVIS BROS. - TRANSIT CORP.
Farm- Hall "F" No. 1

SEC. 12 T. 12 R. 17W
C NW SE

Total Depth. 3642'
Comm. 7-3-59 Comp. 7-13-59
Shot or Treated.
Contractor. Transit Corp.
Issued. 10-17-59

County Ellis
KANSAS



Elevation. 1921' KB

Production. Dry

CASING:

8 5/8" 162' cem w/130 sx.

Figures indicate Bottom of Formations.

| | |
|-----------------------|------|
| clay & shale | 15 |
| rock | 25 |
| sand | 45 |
| shale | 126 |
| sand | 133 |
| shale | 162 |
| shale & shells | 410 |
| sand | 480 |
| shale & shells | 1050 |
| shale (red bed) | 1190 |
| Anhydrite | 1221 |
| shale & shell streaks | 1475 |
| shale | 1820 |
| lime & shale | 2200 |
| lime & shale streaks | 2260 |
| lime & shale | 2835 |
| lime | 3015 |
| lime & shale | 3089 |
| lime & shale streaks | 3128 |
| lime | 3380 |
| lime & chert streaks | 3408 |
| lime & shale streaks | 3452 |
| lime | 3514 |
| Conglomerate & chert | 3543 |
| Conglomerate | 3572 |
| lime | 3642 |
| Total Depth | |

| | |
|------------------|------|
| TOPS: | |
| Anhydrite | 1190 |
| Heebner | 3183 |
| Toronto | 3204 |
| Lansing | 3230 |
| Base Kansas City | 3466 |
| Conglomerate | 3513 |
| Arbuckle | 3572 |

No Electric Log Run.

DST #1 3189-3297', op 1 hr., weak 1 min.
blow. Rec. 25' mud. IBHP 815#/20 mins.
FBHP 710#, both climbing sharply. FP 0#.

DST #2 3291-3352', op 2 hrs., slow steady
blow thruout. Rec. 405' muddy Salt water.
IBHP 1210#/20 mins., FBHP 1035#, FP 235#.

DST #3 3353-3475', op 1 hr., weak 2 min.
blow. Rec. 25' mud, IBHP 585#/20 mins.,
FBHP 180#/30 mins., both climbing sharply
FP 0#.