


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- LEE PHILLIPS OIL CO.  
Farm-Miller No. 1

SEC. 15 T. 12 R.17W  
SE SE SW

Total Depth. 3718 R.B.  
Comm. 1-15-53 Comp. 1-24-53  
Shot or Treated.  
Contractor. Strain Drilling Co.  
Insect. 2-7-53

County Ellis  
KANSAS



CASING:

5/8 set at 174' w/ 85 sx cement

Elevation. 2140 RB

Production. Dry

All Meas. Rotary Bushing:

Figures Indicate Bottom of Formations.

post rock	65
sand rock	85
clay	95
shale	350
shale & shells	530
shale & sand	600
sand	690
sand & pyrite	770
sand & shale	995
red bed & shale	1020
shale	1080
red bed & shale	1349
anhydrite	1390
shale; red bed & shells	1670
shale, lime & shells	1970
lime	2010
lime & shale	2110
lime	2150
lime & shale	2275
lime	2350
lime & shale	2385
lime	2510
lime & shale	2550
shale	2695
shale & lime	2900
lime	2930
lime & shale	3100
broken lime	3150
lime	3670
conglomerate	3718
Total Depth	R.B.

TOPS:

Heebner	3354
Toronto	3375
Lansing	3399
Base KC	3632
Conglomerate	3673

DST: 3675-82 open 30 min. rec. 5'  
mud 15 min. BHP 25#

Schlumberger log run