

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ISERN DRILLING CO., et al
Farm- Schmeidler No. 5

SEC. 17 T. 12 R. 17W
NE NW NW

Total Depth. 3762
Comm. 10-13-54
Shot or Treated.
Contractor.
Issued. 1-1-55

Comp. 10-22-54

County Ellis
KANSAS



Elevation. 2184 DF

Production. 102 bbls.

Figures indicate Bottom of Formations.

post rock	100
shale & shells	675
sand	795
shale & shells	950
sand	1050
shale & shells	1395
anhydrite	1440
shale & shells	1880
salt	1985
shale & shells	2075
lime & shale	2160
shale & shells	2350
lime & shale	2470
shale & shells	2795
lime & shale	2870
shale & shells	3020
lime & shale	3275
lime	3681
conglomerate & chert	3755
Arbuckle	3762
Total Depth	

SCOUT TOPS:

Heetner	3390
Lansing	3436
Conglomerate	3680
Simpson	3710
Arbuckle	3731

Swbd. hole down & drld. float & cmt.
to 3753'. Run Gamma Ray & Neutron log
& perf. 3737-39 w/ 16 holes. Acid.
w/ 500 gals. Comp. for 10 BOPH, 20%
water. Set plug @ 3695' & loaded hole
w/ water. Perf. @ 1375' w/ 4 holes &
squeezed 5 1/4" w/ 500 sx cmt. to surf.
Drld out cmt. & P. O. P.