

KANSAS GEOLOGICAL SURVEY
508 East Murdock
Wichita, Kansas
JUN 20 1970

17-12-17W

P. 75 EC 1/10

WELL LOG

ISERN-WELLS, Schmeidler A #8

Approx. SW NE NW

Section 17-12S-17W

Ellis County, Kansas

ELEVATION: 2168' GL; 2170' DF; 2172' KB.

Figures indicate bottom of formation:

PIPE RECORD:

8 5/8" set at 612'
with 250 sacks 50-50 posmix
4% Jel 3% Calcium Chloride,
200 sacks Sunset Cement.
5 1/2" set at 3685' with
125 sacks common 10% salt cement.

ROTARY COMMENCED: May 4, 1970

ROTARY COMPLETED: May 12, 1970

TOPS

Anhydrite	1380
Topeka	3136
Heebner	3370
Lansing	3418
Conglomerate Chert	3661
Simpson Shale	3667
Arbuckle	3683

0	to	45	rock
		560	shale
		600	red rock
		875	red bed & shale
		1030	sand
		1260	shale
		1377	shale & shells
		1510	shale
		2190	shale & shells
		2545	lime & shale
		2860	shale & lime
		3685	lime & shale
		3685	Rotary Total Depth

STATE OF KANSAS)
COUNTY OF BARTON) ss

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements, and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

W. F. Banks
W. F. Banks, Drlg. Supt.

Subscribed and sworn to before me on this 20th day of May, 1970 .

George A. Meyer
George A. Meyer, Notary Public

My commission expires: February 10, 1970

