

State Geological Survey

WICHITA, BRANCH


KANSAS DRILLERS LOG

S. 17 T. 12 R. 17 ^EW

Loc. NW SW NW

County Ellis

640 Acres
N



Locate well correctly

Elev.: Gr. 2155

DF 2157 KB 2160

API No. 15 — 051 — 21,019
County Number

Operator

Isern Petroleum Co.

Address

Box 486 Ellinwood, Kansas 67526

Well No.

#11

Lease Name

Schmeidler "A"

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Duke Drilling Co.

Geologist

Lewis O. Chubb

Spud Date

3-5-75

Total Depth

3683'

P.B.T.D.

3686

Date Completed

3-11-75

Oil Purchaser

Phillips Petroleum Co.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8 5/8"	28#	246'	Common	135	2% Gel 3% C.C.
Prod. Casing	7 7/8"	4 1/2"	10½#	3681'	Common	100	10% Salt &
					Latex	17	10 bbls salt flush on bottom
D V Tool @ 1376' 400 sacks Common							

LINER RECORD

PERFORATION RECORD

6% Gel

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				Open Hole Completion	3681-3686
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8 EUE	3682	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 3-28-75		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 50 bbls.	Gas None MCF	Water None bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 3681-3686		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Isern Petroleum Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Oil

Well No.

#11

Lease Name

Schmeidler "A"

S17 T12 R17 E
W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Post Rock and Clay	0	50	Anhydrite	1370
Sand	50	70	Topeka	3126
Shale, Clay and Sand Streaks	70	246	Heebner	3364
Shale, Sand Streaks	246	550	Lansing	3412
Shale, Red Bed w/Sand Streaks	550	1160	Conglomerate	3645
Shale and Lime	1160	1370	Simpson Shale	3655
Anhydrite	1370	1412	Arbuckle	3678
Shale & Lime	1412	2212	R.T.D.	3683
Lime	2212	2635		
Lime & Shale	2635	3126		
Lime	3126	3364		
Shale	3364	3368		
Lime & Shale	3368	3412		
Lime	3412	3645		
Chert, Lime, Shale	3645	3678		
Colomite	3678	3683		
R.T.D.		3683		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Signature

General Manager

Title

3-31-75

Date