

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- BIRMINGHAM-BARTLETT DRILLING CO.  
Farm- Bieker No. 1

SEC. 18 T. 12 R.17W  
NW SW SW

Total Depth. 3659'  
Comm. 3-8-55 Comp. 3-17-55  
Shot or Treated.  
Contractor. Brimingham-Bartlett Drlg. Co.  
Issued. 6-4-55

County Ellis

KANSAS



Elevation. 2137 DF

Production. 201 BO

CASING:

8 5/8" 187' w/150 sx cem.  
5 1/2" 3658' w/100 sx cem.

Figures indicate Bottom of Formations.

rock	60
clay-shale	187
shale-shells	480
sand-clay-shale	590
sand	745
shale	805
sand	1045
red bed-shale	1340
Anhydrite	1380
shale-shells	1965
shale-lime	2100
shale-shells	2305
shale-lime	2835
shale	3030
lime-shale	3300
lime	3659

Total Depth RTD

TOPS:

Heebner	3349
Lansing	3392
Arbuckle	3655

DST #1 - 3655-59'. Open 1  
hr. Steady blow. Rec. 30'  
oil & mud. BHP 750# in 15  
min. & going up.

Moved in cable tools & bailed  
down hole & drilled plug.  
Bailed 2 1/2 BOPH for 6 hrs.  
Acidized w/1000 gal. Put well on  
pump.