


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GIEDLER BROTHERS
Farm- Staab No. 1

SEC. 19 T. 12 R. 17W
NE NW SE

Total Depth. 3734'
Comm. 8-19-57 Comp. 8-27-57
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 5-16-59

County Ellis
KANSAS



CASING:

3" 200' cen w/135 sx.
5" 3691'

Elevation. 2119' DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE.

3422-27' white slightly oolitic limestone;
poor porosity w/trace spotted oil
stain.
3441-45' White, soft, chalky limestone, no
porosity, no shows of oil.
3475-81' white, soft chalky to granular
limestone, no shows of oil.
3541-43
& 3561-64' gray-white, finely crystalline
limestone, scattered intercrystalline
to vuggy porosity, trace spotted
oil stain.
3595-3601' & 3623-28', gray-white, finely
crystalline limestone, poor
intercrystalline porosity, trace
spotted oil stain.
3691-98' tan, medium to coarsely crystalline
dolomite, fair intercrystalline to
vuggy porosity, fair to good spotted
oil staining, trace free oil.
3705-25' gray-tan, finely crystalline dolomite,
poor streaked porosity, spotted
black gilsonite stain.
2735-34' light tan finely crystalline dolomite,
cherty, pyritic, no shows of oil.
Rotary Total Depth 3734'

TOPS: SAMPLE

Heebner	3347
Toronto	3371
Lansing-Kansas City	3397
Base Kansas City	3631
Conglomerate	3640
Arbuckle	3689

DST #1 3427-89', op 1 hr, rec. 10' mud,
BHE reached 750 p.s.i. in 20 mins.

DST #2 3537-69', op 30 mins, rec. 15'
slightly oil spotted mud; BHP reached 950
p.s.i. in 15 mins.

DST #3 3593-3629', op 30 mins, rec. 5'
mud; BHP was 0 p.s.i. in 15 mins.

DST #4 3690-3705', op 30 mins, had a weak
blow for 12 mins, rec. 30' slightly oil
cut mud; some free oil in tool; IBHP 235
p.s.i. in 20 mins, FBHP reached 475 p.s.i.
in 20 mins.