

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- FRONTIER OIL CO.

Farm- Giebler

No. 5

SEC. 28 T.12
C E/2 W/2 SW

R. 17W

Total Depth. 3880'

Comm. 5-23-62

Comp. 6-2-62


Shot or Treated.

Contractor. Red Tiger Drilling Co.

Issued. 9-8-62

County Ellis

KANSAS



Elevation. 2122' DF

Production. 83 BOPD, NW

CASING:

8 5/8" 219' cem w/150 sx.

4 1/2" 3870' cem w/225 sx.

Figures Indicate Bottom of Formations.

post rock	90
shale & shells	815
sand	970
shale & redbed	1343
anhydrite	1381
shale, shells, & sand	1534
shale & shells	1946
lime & shale	3132
lime	3341
Heebner	3362
toronto	3386
lansing	3390
lime	3615
cherty conglomerate	3650
arbuckle	3668
arbuckle	3880 RTD
Total Depth	

TOPS:

Anhydrite	1343
Heebner	3340
Toronto	3362
Lansing Kansas City	3386
Base Kansas City	3622
Cherty Conglomerate	3640
Arbuckle	3655