

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock, Wichita, Kansas


Company- ARTNELL CO.
Farm- Karlin No. 1

SEC. 31 T. 12 R. 17W
NE SE NE

Total Depth. 3630'
Comm. 11-14-58 Comp. 11-22-58
Shot or Treated.
Contractor. Vanguard Drlg.
Issued. 4-18-59

County Ellis

KANSAS



CASING:
8" 257'

Elevation. 2060' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	470
gray shale & shells	715
red bed & shells	1100
shale & shells	1290
shale	1570
shale and shells	1840
shale & lime	2185
lime	2535
lime & shale	2690
shale & shells	3025
lime	3330
shale & lime	3405
lime	3555
lime & conglomerate	3630
Total Depth	

TOPS:	
Heebner	3288
Toronto	3308
Lansing	3330
Base Kansas City	3561
Marmaton	3565
Cherty Conglomerate	3578

DST #1 3394-3421', op 90 mins, rec. 30'
of mud, ISIP 960#/20 mins., FBHP 100#/20 mins. IFP 0#, FFP 0#.