

VENUE OIL COMPANY  
 512 North 10th  
 Wichita, Kansas


Company- SUNRAY OIL CORPORATION  
 Farm- Staab No. 2

SEC. 32 T. 12 R. 17W  
 C 1/2 NE NE

Total Depth. 3703  
 Comm. 1-22-52 Comp. 2-6-52  
 Shot or Test No.  
 Contractor. Stickels Drlg Co.  
 Issued. 3-15-52

County Ellis

MANHATTAN



8" 1358'  
 5" 3685'

Elevation. 2124  
 2127 (rod)  
 Production. dry

Figures indicate Bottom of Ferris Lens.

surface clay, post rock  
 40  
 shale 200  
 clay, shells 515  
 shale 740  
 shale, shells 820  
 sand, shells 935  
 shale, shells 1005  
 shale 1090  
 red bed, shale 1170  
 red bed 1348  
 anhydrite 1390  
 shale, shells 2140  
 shale 2240  
 lime, shale 2300  
 lime 2440  
 shale, lime 2725  
 shale 2835  
 shale, shells 3000  
 shale, lime 3125  
 lime 3610  
 lime, shale 3665  
 lime 3689 RTD  
 lime 3703  
 Total Depth

Tops:  
 Heebner 3357  
 Lansing 3399  
 Simpson Shale 3655  
 Arbuckle 3684

DST: 3686-89RTD, open 1 hr.  
 Rec. 30' OH BHP 240#.  
 CO 3689 Test 1 GPH; 300 A;  
 Csg. collapsed @ 2226; Sqz.  
 CO DD 3699; 300 A; T 2 GO /  
 2 GPH;  
 DD 3703 TD. Test 1 BO / 15  
 BHP. D & A