

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ASHLAND OIL & REFG. CO.
Farm - Schmeidler No. 2

SEC. 33 T. 12 R. 17 W
SE SW SW

Total Depth. 3617'

Comm. 3-7-46


Comp. 4-2-46

Shot or Treated. Acidized

Contractor.

Issued. 6-7-47

County. Ellis
KANSAS



CASING:

8 5/8"

1292'

5 1/2"

3616' Cem. w/200 sx.

Elevation. 2084 ft

Production. Phy. Pot. 107 BO,
11 % wtr.

Figures Indicate Bottom of Formations.

surface clay & sand	0-60
shale	260
shale & shells	715
shale	795
sand	925
shale & lime	1000
shale & shells	1265
red bed & shale	1280
anhydrite	1315
shale	1825
shale & shells	1945
shale & lime	2195
lime	2530
lime brkn	2600
lime & shale	2830
shale & shells	2910
lime	2995
lime & shale	3090
lime	3590
lime & shale	3605
shale	3615
lime	3617
Total Depth.	

Acidized w/1000 qts. 3616-17'

Acidized w/1500 gal. 3616-17'

5 BOPH by swab.

Tops:

Lata Winfield	2110
Fort Riley	2170
Florence Flint	2260
Wreford	2360
Council Grove	2370
Cottonwood	2480
Neva	2530
Foratier Group	2600
Elmdale Shale	2680
Emporia -Burlingame	2920
Shawnee	3010
Topeka Series	3050
Douglas	3290
Lans.-Kans. City	3345
Detrital Zone	3580
Cherty Conglomerate	3590
Simpson	3593
Arbuckle Limestone	3615