

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GLENN R. NYE et al

SEC. 1 T. 12 R. 18W

FARM Karlin "A"

NO. 3

LOC. SW SW SE

TOTAL DEPTH 3649'

COMM. 12-22-50


COMP. 1-6-51

SHOT OR TREATED

CONTRACTOR Glenn R. Nye Drilling Co.

ISSUED 2-24-51

COUNTY Ellis



CASINO

8 5/8" 132'

5 1/2" 3648'

ELEVATION 2125

PRODUCTION pot. 443 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

lime stone	85
shale & shells	132
blue shale & iron streaks	630
shale - blue	690
shale & shells	930
sand & shale	1100
red bed & shale	1378
anhydrite	1412
shale & shells	1615
shale & red beds	1650
shale & shells	1745
salt & shale	1875
shale & shells	2050
lime & shale	2375
lime - sandy	2410
shale & lime	2870
shale & shells	2980
shale & lime	3070
shale & lime shells	3162
shale & lime	3200
lime & shale	3218
lime	3250
lime & shale	3280
lime	3315
lime & shale	3325
Heebner shale	3330
shale & lime	3365
lime	3614
Conglomerate	3622
Simpson	3648
Arbuckle	3649
Total Depth	

Tops:

Heebner	3325
Kansas City-Lansing	3368
Conglomerate	3614
Simpson	3621
Arbuckle	3647