


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- WALTERS DRILLING
 Farm- Karlin "A" No. 2

SEC. 1 T12 R. 18W
 NE SE NE

Total Depth. 3767'
 Comm. 10-16-54 Comp. 10-27-54
 Shot or Treated.
 Contractor. Walters Dring. Co.
 Issued. 11-20-54

County Ellis KANSAS



CASING:
 8 5/8" 173' w/ 100 sx cem.

Elevation. 2143' DE

Production. Dry

Figures Indicate Bottom of Formations.

surface	173
shale + shells	689
shale-sand	903
sand	1052
shale-shells	1389
anhydrite	1427
shale-shells	1794
shale-lime	2233
lime	2327
lime-shale	3422
lime	3641
lime-conglomerate	3698
conglomerate	3719
shale-lime	3767
Total Depth	

TOPS:	
Anhydrite	1389
Topeka	3127
Heabner	3360
Toronto	3378
Lansing-Kansas City	3406
Conglomerate	3651
Simpson shale	3750
Arbuckle	3758