

Plotted.
E.M.


BISHOP OIL CO.
Walter No. 1.

SEC.2 T.12 R.18W
CSL SW NE

Plotted Texas CO.

County. Ellis

Total Depth. 3710'
Comm. 9-10-40 Comp. 10-10-40
Shot or Treated.
Contractor.
Issued. 11-2-40



CASING:
10 3/4" 1375'
5 " 3708' P

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sur clay & rock	107	Perforated Lane Wells from
shale	357	3470-81 12 shots
shale & shells	609	tested dry
shale	689	Perforated from 3569-80
sand	819	12 shots, tested dry
shale & shells	880	
sand	1038	
shale red	1161	
shale blue	1191	
shale	1270	
shale & pyrite	1370	
anhydrite	1413	
shale	1707	
shale & salt	1863	
salt	1980	
shale & lime	2020	
salt	2030	
shale & lime	2054	
lime	2245	
shale & lime	2263	
lime	2270	
shale & lime shells	2334	
lime	2365	
lime & shale sdy	2407	
shale & lime	2483	
lime brkn	2526	
shale & lime	2669	
lime	2712	
shale & lime	2807	
lime brkn	2827	
shale & lime shells	2883	
shale	2905	
shale sdy	2920	
lime	2949	
shale & shells	2967	
shale & lime	2990	
lime hrd	3006	
shale & lime brkn	3055	
shale & lime strks	3112	
lime	3203	
lime sft	3205	
oore lime	3205-3215	
shale	3220	
lime	3284	
shale & lime	3317	
lime hrd	3378	
lime w/shale brks	3448	
lime	3472	
lime sft	3478	
lime	3574	
lime sft	3579	
lime	3595	
lime w/shale brks	3650	
conglomerate red	3663	
oore shale red	3663-3668	
shale red	3677	
lime cherty sft	3685	
shale red & green	3703	
lime cherty & shale	3710	
Total Depth.		