


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Hurdock, Wichita, Kansas

Company - LARIO OIL & GAS COMPANY
Farm - Walter "A" No. 1
S.W.D.

SEC. 2 T. 12 R. 18W
CS $\frac{1}{2}$ NW SW

Total Depth. 4186
Comm. 1-25-50 Comp. 3-15-50
Shot or Treated.
Contractor.
Issued. 4-22-50

County. Ellis
KANSAS



CASING:
8 5/8" 215' cem w/125 sx
5 1/2" 3795' cem w/300 sx

Elevation. 2112 *Ind*

Production. S.W.D.W.

Figures indicate Bottom of Formations.

surface clay & sand	85
shale & shells	215
shale	460
shale & sand	510
shale & shells	620
shale, shells & sand	875
sand	1050
shale & shells	1175
red bed & shells	1305
red bed, shale & shells	1365
anhydrite	1400
red bed, shale & shells	1640
shale & shells	1740
salt & shells	1850
shale & shells	1995
shale & lime	2225
lime	2385
lime & shale	2945
lime	2965
shale & lime	3060
lime	3340
lime, shale & chert	3380
lime	3635
lime, shale & chert	3650
lime	4160
Regan sand	4186
Total Depth	

Tops:
Arbuckle 3667 D.F.