


LARIO OIL & GAS CO.
Walter No. 2-C.

SEC. 2 T. 12 R. 18W.
SWo SE

Total Depth. 3643
Comm 5-12-37 Comp. 6-17-37
Shot or Treated.
Contractor. Broadwater Drilling Co.
Issued. 6-26-37

County Ellis.



CASING.

JUN 2 1937

10" 1372' 7" 3641'

Elevation.

Production. Pot. 1424 B.

Figures Indioate Bottom of Formations.

lime	51
shale and shells	101
shale	335
lime and shells	420
shale	480
shale and shells	630
shale and sand	790
shale and lime	845
shale and sand	1030
shale	1040
red rock	1105
shale and lime	1150
broken lime	1198
red rock and shells	1269
shale and shells	1339
lime	1425
shale lime shells	1569
shale and shells	1730
shale and salt	1895
shale and lime	1984
shale and shells	1998
lime	2286
shale and shells	2346
lime	2425
broken lime	2517
lime	2550
shale	2556
shale and lime	2628
shale and shells	2678
lime	2705
shale	2775
lime	2790
broken lime	2845
shale	2887
lime	2918
shale and lime shells	2980
shale and lime	3063
shale	3093
shale and lime	3166
lime	3377
shale	3395
shale and lime	3413
lime	3556
shale	3570
lime	3596

shale	3606
lime	3620
cored 3620-30	
cored 3630-37 $\frac{1}{2}$	
standardized 3637 $\frac{1}{2}$	
T. Siliceous	3635
lime	3643
Total Depth.	

1500' oil 1 hour.
3000' oil Total
Potential 1424 bbls oil.

T. siliceous 3635
cored from 3630-37
5' Rec.
saturated.