

4-12-18W
C S/2 SW SE

DRILLERS' WELL LOG

DATE COMMENCED: June 11, 1980
DATE COMPLETED: June 18, 1980

Icer Addis
JOHNSON #1
S/2 SW SE
Sec. 4-T12-18W
Ellis County, Ks.

K. C. S. LIBRARY

0 - 207' Surface Soil & Post Rock
207 - 273' Shale
273 - 869' Shale & Sand Streaks
869 - 1069' Sand
1069 - 1407' Shale
1407 - 1452' Anhydrite
1452 - 2309' Shale
2309 - 3119' Shale & Lime
3119 - 3355' Lime
3355 - 3358' Shale
3358 - 3403' Lime & Shale
3403 - 3649' Lime
3649 - 3684' Lime, Shale, Congl.
3684 - 3715' Dolomite
3715' RTD


ELEVATION: 2118 K.B.

FORMATION DATA

Anhydrite 1407'
Topoka 3119'
Heelner 3355'
Toronto 3383'
Lansing-K.C. 3403'
Base-K.C. 3649'
Conglomerate 3670'
Arbuckle 3684'
RTD 3715'

Surface Pipe: Set used
8-5/8" pipe, 28# at 207
w/150 sacks 50/50 pozmix,
2% gel, 3/cc.

ICER ADDIS
DRAWER #8038 #1 JOHNSON 4-12-18W
WICHITA, KS. 67208 C S/2 SW SE
CONTR DUKE DRILLING CO., INC. CTY ELLIS
GEOL RICHARD FOLEY FIELD BEMIS-SHUTTS
E 2118 KB CM 6/11/80 CARD ISSUED 7/4/80 IP D&A/ARB
API 15-051-21,975 6/18/80



SMP	TOPS	DEPTH	DATUM
ANH	1407	+ 711	
TOP	3119	-1001	
HEEB	3355	-1237	
TOR	3383	-1265	
LANS	3403	-1285	
BKC	3649	-1531	
CONG	3670	-1552	
ARB	3684	-1566	
RTD	3715	-1597	
NO LOG			

8-5/8" 207/150sx

DST (1) 3460-95/30-30-30-30, REC
40' MW, SIP 1054-1044#, FP 43-53#
DST (2) 3588-3650/30-30-30-30, REC
270' MW, SIP 897-835#, FP 74-
117/149-181#
DST (3) 3686-3693/30-30-30-30, REC
10' WTRY M, NS, SIP 1013-981#,
FP 32-11#