

DRILLERS' WELL LOG

DATE COMMENCED: April 16, 1979
DATE COMPLETED: April 23, 1979

Raymond Oil Co., Inc.
STACKHOUSE # 1
SW NE SW
Sec 7, T12S, R18 W
Ellis County, Ks.

0 - 50 Clay, Sand, Post Rock
50 - 100 Post Rock
100 - 975 Shale
975 - 1190 Sand
1190 - 1508 Shale
1508 - 1553 Anhydrite
1553 - 3215 Shale & Lime
3215 - 3443 Lime
3443 - 3447 Shale
3447 - 3489 Lime & Shale
3489 - 3734 Lime
3734 - 3740 Lime & Shale
3740 RTD

ELEVATION: 2195 K B

FORMATION DATA

Anhydrite	1508
Topeka	3215
Heebner	3443
Toronto	3469
Lansing-KC	3489
Base KC	3734
RTD	3740

SURFACE PIPE: Set
used 10 3/4" pipe
@ 217' w/135 sacks
common, 2 % gel,
3 % cc.

A F F I D A V I T

State of Kansas
County of Barton) ss.

Bill Draney, of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 24 day of April, 1979