

DRILLERS' WELL LOG

DATE COMMENCED: September 15, 1975
DATE COMPLETED: September 22, 1975

F & M Oil Co.
SCHMEIDLER # 1
SW NW NE of Sec 9-T12-R18W
Ellis County, Kansas

ELEVATION: 2147' K.B.

FORMATION TOPS

0 - 60'	Post Rock and Clay
60 - 1160'	Shale, Shells and Sand Streaks
1160 - 1436'	Red Bed
1436 - 1480'	Anhydrite
1480 - 1995'	Shale and Shells
1995 - 3382'	Lime and Shale
3382 - 3386'	Shale
3386 - 3425'	Lime and Shale
3425 - 3688'	Lime
3688 - 3720'	Lime, Chert, Shale
3720'	RTD

Anhydrite	1436'
Heebner	3382'
Lansing	3425'
Conglomerate	3688'
RTD	3720'

SURFACE PIPE:

Set 206' of 8 5/8", 28# used
pipe w/125 sacks Common, 2% Gel,
3% cc.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1975

CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Wayne Dobbs, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Wayne Dobbs

Subscribed and sworn to before me this 23rd day of September, 1975.

Alvord M. Hogue

Notary Public

My Commission Expires: April 11, 1978