

1100000.  
E.M.


Plotted by S. CO.

GULF OIL CORP.  
F.A. Denman No. 1.

SEC. 11 T. 12 R. 18W  
CN 1/2 SE SW

Total Depth. 3680'  
Comm. 11-14-39 Comp. 12-10-39  
Shot or Treated. 12-10-39 2000 Gals.  
Contractor.  
Issued. 1-6-40

County. Ellis



CASING:  
8 5/8" 1393'  
5 1/2" 3670'

Elevation.

Production. Pot. 2970 B.

Figures Indicate Bottom of Formations no wtr, depthograph

lime chalky	110
shale blue sticky	235
blue shale & shells	515
shale blue sticky	635
sand	665
shale blue & shells	768
sand	860
shale blue & sand shells	
hard	935
shale sdy	1050
sand white	1100
shale red	1150
red bed & lime shells	1394
anhydrite	1454
shale red	1460
anhydrite	1483
shale red	1535
shale gy	1640
shale blue & shells	1785
salt	1970
shale blue & shells	1995
anhydrite&sm shale brks	2095
lime & gy shale	2145
lime & blue shale	2230
shale & lime shells	2300
limo	2308
shale & lime	2368
lime & shale brks	2461
lime w/red shale brks	2471
lime & blue shale brks	2490
lime & gy shalo	2575
shalo & lime shells	2625
lime gy	2650
limo & shale brks	2722
lime	2777
shale & lime	2822
lime	2874
shale blue & red	2960
dk shalo & lime shells	3040
shalo & limo	3103
shale & shells	3160
lime	3245
lime hrd	3280
lime	3490
lime w/strks blk shale	3525
lime	3662
shale green	3670
lime	3680
Total Depth.	

Arbuckle lime 3670-80