

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL CO.

Farm - Kocornor

No. 1

SEC. 11 T. 12 R. 18 W
C. 1/2 NE SE

Total Depth. 3641'

Comm. 6-4-47

Comp. 6-19-47


Shot or Treated.

Contractor. Glenn W. Pool

Issued. 8-16-47

County. Ellis

KANSAS



CASING:

8 5/8" OD

1378' Com. w/450 sx.

5 1/2" OD

3639' Com. w/100 sx.

Elevation. 2130 feet sh.

Production. Pot. 356 BO, no wtr.

Figures Indicate Bottom of Formations.

surface rock	95
sand	135
shale - shells	660
shale sand	1165
red bed	1375
anhydrite	1379
sand	1715
shale salt shells	2016
limo & shale	2226
limo	2380
limo w/cherty strks	2410
limo & shale	3295
limo cherty	3330
limo & shale	3485
limo	3555
shale limo	3638
dolomite	3641
Total Depth.	

Tops:

Lansing	3377
small show oil	3421-24'
small show oil	3475-78'
very good odor & sat.	
	3465-76'
good stain	3534-41'
good stain	3550-55'
Arbuckle	3638

Drld plug & drld deeper to 3641'

T.D. Fillup 1000' 2 hrs.

Swbd down & then swbd 55 BO in

2 hrs. 100' off btm., no wtr.