

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas.

THE CARTER OIL CO.,
A.J. Koerner No. 1.

SEC. 11 T. 12 R. 18W.
NWc SE
330' fr N and W. lines.
NW NW SE

Total Depth. 3678
Comm. 7-3-37 Comp. 7-28-37
Shot or Treated.
Contractor. Robey Drlg. Co.
Issued. 10-9-37

County Ellis.

CASING.

103/4" 1403'
7" 3672'

Elevation.

Production. Pot. 2054 B.

Figures Indicate Bottom of Formations.

clay sand	40
sand shale	222
shale and shells	680
shale	840
lime	890
sand	1040
lime	1150
red rock	1175
shale and shells	1345
shale	1395
anhydrite	1490
red bed and shells	1585
shale and shells	1945
shale lime shells	2045
shale and lime	2090
lime	2150
shale and lime	2255
lime hard	2 320
lime	2460
broken lime	2530
lime shells	2630
lime	2865
broken lime	2935
lime and shale	3030
shale and shells	3095
lime shells	3155
lime	3470
broken lime	3530
lime	3635
shale	3653
shale and lime	3668
lime	3678
Total Depth.	

Small show oil 3150-60
small show oil 3260-70
small show oil 3345-55
show oil 3450-55
small show oil 3590-3600
show oil 3673-77

Siliceous lime 3673-3678
Simpson 3660-3673
K.C. Lansing 3410-3660
Douglas 3375-3410
Topeka 3110-3375