


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CARTER OIL CO.
A.J. Koerner No. 2

SEC 11 T. 12 R. 18W.
NE NW SE

Total Depth. 3673
Comm. 8-13-37 Comp. 9-15-37
Shot or Treated. 1000 gal 3668--73
Santractor. Company Tools.
Issued. 10-23-37

County. Ellis.



CASING. Rotary 3669
Cable 3673

103/4" 1380'
6" 3669'

Elevation.

Production. Pot. 1719 B.

Figures Indicate Bottom of Formations.

sand and shale	80
sdv lime and shale	400
lime shells & shale	680
shells shale and sand	1090
lime and shale	1381
shale	1396
lime	1430
red bed	1490
shale	1551
shale and shells	1760
shale and salt	1980
lime and shale	2173
shale and shells	2253
lime	2414
shale and shells	2467
lime and s hale	2590
lime	2629
shale and lime	2864
shale	2910
broken lime	2949
lime	3055
shale and shells	3105
lime	3612
lime and shale brks	3640
lime	3652
shale groon	3662
shale and lime	3669
lime	3673
Total Depth.	

Siliceous lime 3668-3673

Top Topoka 3103
Small s how oil 3245-60
small show oil 3315-30
Top Douglas 3380
Top Kansas City Lansing 3405.
Good show oil 3420-30
Good show oil 3443-58
small show oil 3535-3605.
Top Decorah Simpson 3655
Top Siliceous 3668
Good show oil 3668-73