

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


PHILLIPS PETRO.
A.V. Staab No. 1.

SEC. 11 T. 12 R. 18W
NW 1/4 NE

Total Depth. 3631'
Comm. 4-14-37 Comp. 5-26-37
Shot or Treated. 2000 Gals. Acid.
Contractor.
Issued. 11-13-37 ROTARY

NOV 13 1937

County. Ellis



CASING:

10" 1237'
7" 3609'
5" 3630' perforated liner

Elevation.

Production. Pot. 2200 B.
No wtr.

Figures Indicate Bottom of Formations.

shale	235
shale & shells	465
shale	860
wtr sand	1020
shale & sand	1080
sand	1090
sand & shale	1100
shale	1110
shale & shells	1135
red rock	1200
sand red	1220
red rock	1237
red bed	1360
anhydrite	1385
red bed, shale & gyp	1457
shale, gyp & shells	1838
shale	1905
shale & lime shells	1970
brkn lime	2280
shale & shells	2320
shale & lime shells	2380
brkn lime	2540
shale & shells	2600
brkn lime	3087
sticky shale blue	3096
brkn lime	3267
shale blue	3275
lime	3368
shale	3425
brkn lime	3609
Siliceous lime	3610
shale green	3624
2650' oil in hole 13 hrs.	
Siliceous lime	3631
Total Depth.	