

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.

CARTER OIL CO.  
A.V. Staab No. 3.

SEC. 11 T. 12 R. 18W  
SEo NW  
330' fr S & E L E $\frac{1}{2}$  NW  
SE SE NW  
County. Ellis

Total Depth. 3655'  
Comra. 5-12-37 Comp. 6-9-37  
Shot or Treated. 1500 Gals. 3649-3655  
Contractor. Robey Drlg. Co.  
Issued. 8-21-37 Rotary 3655



Elevation.

CASING:  
10" 1377'  
7" 3648'

Production. Pot. 1002 B.  
No wtr.

Figures Indicate Bottom of Formations.

cellar	8
clay	15
shale, shells	630
shale	865
lime	885
sand	1035
sand hrd	1080
sand	1145
red bed, shells	1364
anhydrite	1378
lime	1390
anhydrite	1425
red bed, shells	1500
red rock, salt	1670
salt	1855
salt, shale	1965
lime, shale	2000
lime	2590
lime brkn	2660
lime	2733
lime, shale, shells	2805
lime brkn	2854
shale, shells	2970
lime	2995
shale, shells	3060
shale	3070
lime	3157
brkn lime	3200
lime	3225
dolomitic lime	3240
lime hrd	3274
lime	3405
lime brkn	3410
shale	3415
brkn lime	3420
lime	3605
shale red	3625
lime	3650
lime cored	3655
Total Depth.	

Siliceous lime 3649-3655  
Topeka Top 3070