


THE CARTER OIL CO.
A.V.Staab No. 4.

SEC. 11 T. 12 R. 18W
SW SE NW
330' fr W & SL E $\frac{1}{2}$ NW $\frac{1}{4}$

Total Depth. 3656'
Comm. 6-4-37 Comp. 6-28-37
Shot or Treated. 1500 Gals. 3651-56
Contractor. Robey Drlg.Co.
Issued. 8-21-37 Rotary O-3656

County. Ellis



CASING:
10 $\frac{3}{4}$ " 120'6"
7 " 3651'

Elevation.

Production. Pot.1074 B.
No wtr.

Figures Indicate Bottom of Formations.

surface	265
shale & shells	825
lime	875
sand	1040
lime	1070
shale & shells	1160
red bed & shells	1285
brkn lime	1372
anhydrite	1390
red bed	1420
salt	1687
shale	1946
shale & lime	2035
lime	2510
lime & shale	2570
lime	3030
shale	3070
lime	3643
shale green	3651
lime	3656
Total Depth.	

Siliceous Limo 3651-3656