

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - HEATHMAN DRILLING
Farm WIESNER No. 1

SEC. 11 T. 12 R18W
SW/4 SE/4 SW/4

Total Depth. 3694

Comm. 12-17-49

Comp. 12-27-49


Shot or Treated.

Contractor. HEATHMAN

Issued. 2-4-50

County. Ellis

KANSAS



Elevation. 2156

Production. dry D&A

CASING:
8 5/8 at 156' cem w/ 100 sx

5 1/2" at 3675 cem w/ 175 sx

Figures indicate Bottom of Formations.

sand lime shells	130
shale	750
sand	845
shale	915
sand	1080
shale and shells	1397
anhydrite	1429
shale and shells	1680
shale	2080
shale and lime	3230
lime	3336
lime and shale	3435
lime	3513
lime and shale	3675
lime	3694

Total Depth

Tops:

Anhydrite	1397
Hebner	3353
Lansing	3402
Simpson	3656
Arbuckle	3673
R.T.D.	3675
C.T.D.	3694

D & A 1-10-50 Pipe to be pulled and hole plugged on approximately 1-14-50

DST #1 -3492 to 3505- Open 30 min- rec 30' mud. DD to 3675 1/2- got 125' rotary mud in 45 min. DD to 3676 - Swabbed 15-29 wtr and 11.76 oil- 4 hrs. Swabbed 41.0 wtr and 11.76 oil- 12 hrs. DD to 3686- got 5 1/2 bwph plus 1 boph. DD to 3694 TD- Swabbed 7 1/2 bfph- 7 hrs -(44 bw & 3 1/2 bo) Last 4 hrs got no oil. Plug @ 3464'- Perforated 23 shots 3425-34- Bailed 2 bwph Moved cable tools off and pull pipe and plug