


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CARTER OIL CO.
A. Wiesner No. 1.

SEC. 11 T. 12 R. 18W.
SEc SE

Total Depth. 3622
Comm. 2-7-38 Comp. 2-27-38
Shot or Treated.
Contractor. Robey Drlg. Co.
Issued. 4-2-38

County Ellis.



CASING.

Rotary.

103/4" 1192
6" 3618'

Elevation.

Production. Pot. 1539 B.

Figures indicate Bottom of Formations.

cellar	10
rock, clay	45
sand	70
shale gravel	435
sand and shale	490
sand	665
sand and shale	715
shale	800
lime	860
sand	1075
red rock	1355
anhydrite	1400
shale	1495
shale red rock	1660
broken lime	1675
shale lime shells	1780
shale	1820
shale lime	2010
shale broken lime	2020
lime	2155
shale	2200
lime	2275
shale	2295
lime	2540
shale broken lime	2595
lime	2620
broken lime shale	2685
lime	2720
shale broken lime	2795
shale lime shells	2880
shale lime	2950
broken lime shale	2990
broken lime	3155
lime grey	3190
lime hard	3285
lime	3377
lime cored	3383
lime	3428
cored lime	3432
lime	3611 $\frac{1}{2}$
cored lime	3617
cored green shale	
Arbuckle	3622

Total Depth.

Sat. 3372-75
good show oil 3375-79
slight spotted saturation 3393-96
slight spotted saturation 3426-30

Top Simpson 3604
Top Arbuckle 3613

Arbuckle 3618-3622
Simpson 3604-3618