

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


Company- CARTER OIL CO.
Farm- Staab No. 10

SEC. 11 T. 12 R.18W
CE $\frac{1}{2}$ NW NE

Total Depth. 4190'
Comm. 6-29-50
Shot or Treated.
Contractor.
Issued. 4-26-58

DEEPENING RECORD:
Comp. 5-30-50

County Ellis
KANSAS



Elevation. 2123

Production 9 BOP / 50 BW

Case:

10 3/4" 1375' w/700 sx cem
7" 3651' w/175 sx cem.

Figure 1. Litho Section of Well Logs

surface, rock, clay	25
post rock, shale	105
shale, shells	345
shale	465
shale	490
shale, sand	540
shale, shells	625
sand	690
sand, iron	760
shale, shells, red bed	790
iron, sand	885
sand	1040
red bed, shale	1367
anhydrite	1410
red bed, shale, shells	1585
shale, shells	1730
salt, shells	1930
shale, shells	2000
lime	3380
shale, lime	3065
lime	3659
Total Depth	

TOPS:

Anhydrite	1367
Heebner	3328
Dodge	3347
Lansing	3382
B/Kansas City	3617
Simpson Dolomite	3632
Simpson shale	3641
Arbuckle	3650

DEEPENING RECORD:

Pröd. -SWD
T.D. -4190'
Comm. -3-26-52
Comp. -3-31-52

Deepened from 3655 to 4190'

Top Granite Wash 4185

5 1/2" liner from 3619 to 3866'
w/100 sx cem.

Receptivity test accepted 207 bbls.
salt wtr. in 23 mins. @ 22 pts.
vacuum.