


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - AYLWARD PRODUCTION CO., ET AL
Farm - Jensen No. 2

SEC. 12 T. 12 R. 18 W
CW/2 SE SW
890' S of Jensen #1 400' EWL
E $\frac{1}{2}$ SW $\frac{1}{4}$
County. Ellis
1320 FSL KANSAS
2900 FEL
KGS-DRL NAD83
LEO Web



Total Depth. 3692'
Comm. 5-15-45 Comp. 6-11-45
Shot or Treated. 1000 gals acid.
Contractor. Aylward Prod. Co.
Issued. 7-21-45

CASING:
8 5/8" 1440'
5 1/2" 3685'

Elevation.

Production. Est. 200 B.

Figures Indicate Bottom of Formations.

rock & shale	0-75
shale & sand	345
shale & shells	615
sand	620
shale & shells	680
sand	790
shale	875
shale blue	907
sand	1060
red rock	1095
shale & shells	1285
red rock	1400
anhydrite lime	1430
anhydrite	1445
red rock & shale	1665
shale	1745
salt	1920
shale & shells	2125
lime	2140
lime & shale	2390
lime	2440
lime & shale	2575
lime brkn	2650
lime	2710
red rock	2735
lime	2765
lime brkn & shale	2865
lime brkn	3150
lime	3180
lime & shale	3220
lime	3390
shale & lime	3397
lime	3494
shale	3512
lime	3575
lime & shale	3610
lime	3680
lime & shale	3686
lime	3692
Total Depth.	

Tops:
K.C. lime 3390
Arbuckle 3685

Show oil at 3685
1 2/3 bailers per hr at 3688, no
wtr while drilling from 3688
to 3692', hole filled up 650'

Acidized w/1000 gals.