

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


4954 FSL and 2312 FEL LEO WEB 11/28/2022

Company - SHELLEY OIL CO.
Farm Joseph G. Dinkel No. 1.

SEC. 13 T. 12 R. 18 W
NWc NE
330' FNL 330' FNL NE₂

Total Depth. 3690
Comm. 3-30-46 Comp. 4-23-46
Shot or Treated.
Contractor. Claude Wontworth
issued. 6-22-46 Rotary O-3684
Cable 3684-3690

County. Ellis
KANSAS



CASING:
13 3/8" 142' Cem.
8 5/8" 1425' Cem.
5 1/2" 3680' Cem.

Elevation. _____

Production. Pot. 348 B

Figures indicate Bottom of Formations.

top soil 0-2
lime brkn wh 20
shale 40
shale & sand 135
lime 145
shale 305
shale & shells 810
shale 870
shale & shells 915
shale & gravel 1080
shale & shells 1140
shale, shells &
red rock 1185
red rock 1312
red rock & shells 1418
anhydrite 1455
red bed 1580
shale & shells 1880
salt & shale 1900
shale & shells 2080
shale & lime 2500
lime sdy 2560
lime & shale 2595
sand 2600
lime & shale 3260
lime 3295
lime & shale 3387
lime 3042
lime & shale 3669
dolomite gy sdy 3672
shale green 3679
dolomite gy &
brown coarsely
xlyn, porous &
saturated 3684
dolomite brown
cherty, spotted
por & sat 3686
bailed & tested 6
hrs, 1/2 BO, no wtr
dolomite gy &
brown cherty,
spotted por &
sat., no inc. in
oil 3687
dolomite brown, por.
& sat. 800' OIH in
30 mins. 1800' OIH
in 1 1/2 hrs. 2100'
OIH in 3 hrs, no
wtr. Swbd through
5 1/2" csg 1000' off
bottom 4 hrs.,
70 BO, no wtr 3690
Total Depth

Tops:
Ft. Dodge Lime 3386
Lansing Lime 3421
Simpson Series 3669
Arbuckle Lime 3679
Porous & saturated 3679-84
Spotted por. & sat. 3684-87
Porous & sat., 2100'
OIH in 3 hrs., no
water 3687-90