


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RAYMOND OIL COMPANY, INC.
Farm- Keberlein No. 1

SEC. 2 T. 12 R. 19W
NW SW NE

Total Depth. 3720'
Comm. 9-25-61 Comp. 10-3-61
Shot or Treated.
Contractor.
Issued. 1-6-62

County Ellis KANSAS



CASING:
8 5/8" 244' cem w/200 sx.

Elevation. 2138' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	244
shale	880
shale, shells, redbed	950
sand	1100
red bed & shale	1486
Anhydrite	1526
shale & shells	2210
shale w/lime	2250
lime & shale	3293
lime	3421
lime & shale	3717
Arbuckle	3720 RTD
Total Depth	

TOPS:

Anhydrite (driller's)	1526
Topeka	3267
Haebner	3388
Toronto	3409
Lansing	3431
Base Kansas City	3637
Conglomerate	3697
Re-Worked Simpson	3709

DST #1 3454-3490', op 1 hr, weak steady
blow thruout test, rec. 255' watery mud
w/specks of oil. ICIP 1070#/20 mins.
IFP 35#, FFP 140#, FCIP 1030#/20 mins.