

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- ICER ADDIS
Farm- Alois Younker

No. 2

SEC. 9 T. 12 R. 19W
NW NE SE

Total Depth. 3862'
Comm. 8-26-60 Comp. 9-6-60
Shot or Treated.
Contractor. Triangle Drlg.
Issued. 10-29-60

County Ellis
KANSAS



CASING:
8 5/8" 185' cem w/135 sx.

Elevation. 2221' KB

Production. Dry

Figures Indicate Bottom of Formations.

clay & post rock	85
shale	150
sand	160
shale	185
shale & clay	700
shale & sand	730
sand	820
shale & sand	1285
red bed	1534
Anhydrite	1581
shale & shells	2100
lime & shale	2500
limestone	2625
lime & shale	2737
limestone	2845
lime & shale	3217
limestone	3483
shale	3490
limestone	3729
lime, chert & shale	3806
Conglomerate	3812
Dolomite	3862 RTD
Total Depth	

TOPS:

Anhydrite (driller's)	1534
Topeka	3217
Heebner	3448
Toronto	3465
Lansing	3490
Base Kansas City	3729
Chert Conglomerate	3806
Arbuckle	3812