


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HERNDON DRILLING CO.
Farm - Bemis "A" No. 1

SEC. 15 T. 12 R. 19W
NE NE NE

Total Depth. 4015
Comm. 11-15-48 Comp. 11-30-48
Shot or Treated.
Contractor. Herndon Drlg.
Issued. 2-12-49

County. Ellis
KANSAS



Elevation. 2225 ft.

CASING:

8 5/8" OD 208' cem w/100 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	205
shale, shells	510
shale, shells, sand	1400
shale, shells	1585
anhydrite	1635
shale, red bed	1970
shale, salt	2160
shale, lime	2260
lime	2340
lime, shale	2550
lime	2800
lime, shale	3355
lime	3440
lime, chert	3485
lime	3790
lime, shale	3840
lime, chert	3858
conglomerate	4005
lime	4015
total depth	

Tops:

H...ner	3503
Brown lime	3524
Kansas City	3548
Slight stain	3575-90
Arbuckle	3862

Plugged. Bottom plug set
@ 200' w/15 sx cement. Top
plug set @ 30' cem w/10 sx bulk
cement.