

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


CORALENA OIL CO.
Glathart No. 1.

SEC. 16 T.12 R.19 W
SEC SE

DISCOVERY WELL

Total Depth. 3560'
Comm. 6-22-43 Comp. 7-5-43
Shot or Treated.
Contractor.
Issued. 8-7-43

County. Ellis



CASING:
10 $\frac{3}{4}$ " 125'
5 $\frac{1}{2}$ " 3545'

Elevation.

Production. Pot. 275 B. Phy.

Figures Indicate Bottom of Formations.

surface clay	0-74	Tops:	
shale & shells	658	Topeka	3235
sand, strks shale	751	Dodge	3448
shale & shells	875	Kansas City	3500
sand, shale, shells	1247		
red rock, shale, shells	1480		
anhydrite	1536		
shale & shells	1596		
shale & pyrite	1697 ✓		
shale & shells	1865		
lime & shale	1892		
salt & shale	2047		
shale & shells	2147		
shale, strks anhydrite	2205		
lime & shale	2315		
lime	2357		
lime & shale	2509		
lime	2593		
lime & shale	3030		
lime	3058		
lime & shale	3078		
lime SIM @ 3104	3195		
lime, red rock, shale	3235		
lime brkn	3280		
lime, spotted saturation	3295		
lime gy, red rock, shale	3369		
lime, spotted saturation	3374		
lime gy	3442		
shale red, green, blue	3448		
lime wh dense	3451		
lime, saturation	3452		
lime wh	3468		
red rock & shale	3500		
lime wh, fossiliferous	3504		
lime, good saturation & porosity	3514		
lime wh	3551		
lime, saturation	3556		
lime	3560		
Total Depth.			

Drld plug & well filled