

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CRESCENT OIL & GAS CORPORATION

SEC. 17 T. 12 R. 19W
 LOC. SE NE NE

FARM Spreen

NO. 1

COUNTY Ellis

TOTAL DEPTH 3890

COMM. 7-6-63


COMP. 7-17-63

SHOT OR TREATED

CONTRACTOR Red Tiger Drllg.

ISSUED 6-25-66

KANSAS



CASING

20 10 3/4" @ 240' w/175 SX.
 15 8
 12 6
 13 5 1/2" @ 3382' w/250 SX.

ELEVATION 2243' KB

PRODUCTION FMP 206 BOPL, NW

FIGURES INDICATE BOTTOM OF FORMATIONS

FORMATION	FROM	TO	REMARKS
Rock	0	25	
Rock, Clay & Shale	25	240	
Shale	240	570	TOPS: SAMPLE
Gray Shale w/Sand Stringers	570	850	
Shale	850	980	Anhydrite 1579
Red Bed Streaks	980	1070	Topeka 3252
Sand	1070	1270	Heebner 3481
Red Bed & Shale	1270	1576	Toronto 3502
Anhydrite	1576	1620	Lansing 3522
Shale & Shells	1620	2123	Base K. C. Marm 3756
Shale & Lime	2123	2680	Conglomerate 3811
Sand Lime & Shale	2680	2755	Arbuckle 3827
Lime & Shale	2755	3420	
Lime	3420	3711	
Lime & Shale	3711	3810	
Chert	3810	3825	
Arbuckle	3825	3890	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Dennis V. Head

Maximo Head

Subscribed and sworn to before me this 19th day of July, 1963.

John Miller

Notary Public

My Commission Expires: