

CORAEMA OIL CO.
 Reeder No. 1.

SEC. 22 T. 12 R. 19 W
 CNW NW

County. Ellis

Total Depth, 3887' PB 3555'
 Comm. 8-1-43 Comp. 8-18-43
 Shot or Treated.
 Contractor,
 Issued, 10-9-43

CASING:
 125' Cem.
 10 3/4"
 5 # 3579' Cem.

Elevation.



Production. Dry

Figures Indicate Botto of Formations.

clay	0-35	lime	3798
shale & shells	136	lime, red rock, shale	3828
sand & shale	236	lime	3833
shale & shells	525	conglomerate &	
sand	555	variegated shale	3864
shale & shells	679	dolomite cherty,	
sand & shale	736	stain & porosity	3887
red rock, sand, shale	1020	Total Depth.	
shale & shells	1270		
red rock, shale, shells	1507		
anhydrite	1558		
shale & shells	1845		
red rock & shale	1940	Plugged back	3555
salt	2080		
shale	2146	Perf. 3522-3536 w/34	
lime & shale	2209	shots	
shale	2340	Acidized w/2000 Gals.	
lime & shale	2369	Made 10 BW & no oil	
lime	2399	Dry & Abnd.	
shale & shells	2440		
sand & shale	2455		
shale	2507		
lime	2513		
lime & shale	2560		
shale	2650		
lime & shale	2635		
shale-striks lime	2672		
lime & shale	2926		
SIM at 2884 OK			
shale & shells	3007		
lime & shale	3048		
shale	3100		
shale & shells	3259		
lime	3267		
lime & shale	3335		
lime	3361		
lime & shale	3398		
SIM 3365=67			
lime	3429		
lime & shale	3449		
red rock & shale	3458		
lime wh	3478		
shale variegated & strks			
of lime, pyrite	3520		
lime	3523		
lime, spotted sat.-dead			
oil, poor porosity	3534		
lime	3539		
lime & shale	3570		
lime, spotted sat.	3574		
lime gy hd	3583		
lime, saturation	3590		
lime & shale	3649		
lime, spotted sat-wtr	3651		
lime hd, strks shale	3700		
lime, spotted sat-wtr	3707		

Tops:
 Topoka 3247
 Dodge 3458
 K.C. 3520